

TATA INSTITUTE OF FUNDAMENTAL RESEARCH

An Autonomous Institution of the Department of Atomic Energy, Government of India (A Deemed University)
Plot No.36/P, Gopanpally Village, Serilingampally Mandal, Ranga Reddy District. Hyderabad, Telangana, India.

PIN 500 046

Phone: 040-20203010, Email: rajasekharr@tifrh.res.in

Ref:TIFR/PD/CA21-169/211154

December 07, 2021

ENQUIRY

To
The Bidders / Suppliers

=> By Speed Post/Courier

Dear Sirs

Please let us have your Quotation for the following:

S.No.	Item Description	Qty	UOM
1	Supply of 1.5 TR Split Hi wall Air Conditioning unit Specifications: Power Supply : 230V +/-10%, 50Hz Star Rating: 5 Inverter Technology Refrigerant :R410/R 32 Compressor: Rotary /Scroll Condenser Evaporator Coil: Copper (Units shall be supplied with all accessories provided by the manufacturer (i.e. Cu Pipe, Remote, Manuals, Warranty, etc.) Make: LG/Daikin/Voltas/Blue Star/Equivalent Approved	4.00	NO
2	Installation, Testing and commissioning of above 1.5 TR Split Hi wall Air Conditioning indoor outdoor unit (i.e. Sl.No.1)	4.00	NO
3	Supply and installation of suitable size MS Stand for Outdoor unit of above 1.5 TR Split Air Conditioning unit (i.e. for Sl.No.1)	4.00	NO
4	Supply, Installation, Testing and Commissioning of Additional Cu piping (as recommended by Manufacturer) for supply and return of refrigerant suitable for Sr. No. 1 Split Hi Wall ACs with 19 mm thick class 'O' nitrile rubber insulation	10.00	MTR
5	Supply Installation of 1" Heavy Duty PVC Pipe for drain	10.00	MTR
6	Supply, Installation, Testing and Commissioning of suitable timer controller for sequence operation of above mentioned Sr. 1 Air Conditioners	2.00	NO
7	Supply, laying, termination, testing commissioning of 4C X 2.5 sq.mm FR PVC insulated copper conductor flexible cable as per IS 694 with latest amendments Make: Polycab/Havells/Finolex/RR Cables	20.00	MTR

NOTE :

The quotation should valid for 60 Days.

Please submit the quotation as per attached BOQ duly signed and stamped on Letterhead.

Please mention your GST Registration numbers on the quotation, proforma Invoice and Bills. Quotation should indicate make, delivery period, guarantee/warranty exact taxes applicable, etc.

The payment will be made only after delivery of the supply, satisfactory installtion, commissioning and performance of the item/equipment. No Advance payment will be made except in case of furnishing valid Bank Guarantee from any nationalized/scheduled bank the B. G. shall be valid till the complete delivery is made at the site.

Quotation should be submitted in sealed envelope duly superscribing our enquiry reference and due date.

TIFR is a public funded research institute and is entitled to concessional rate of GST @ 5% for certain items supplied for research purpose vide notification no. 47/2017 dated 14th Nov, 2017. The offer should be submitted after fully considering the above notification.

Quotation sent by hand delivery / courier are to be deposited in the Tender Box kept at the Main Gate after obtaining stamp, date and signature of the Security Officer.

Due Date for submitting your offer is 17/12/2021.

Yours faithfully


RAJASEKHAR R.
Head-Technical Services



BOQ for Supply, Installation, Testing & Commissioning of Air Conditioning works for Hostel Block-II at Plot-B, TIFR Hyderabad					
Sl. No.	Item Description	Unit	Qty (A)	Rate/Unit (B)	Amount (C)=AXB
1	Supply of 1.5 TR Split Hi wall Air Conditioning unit Specifications: Power Supply : 230V +/-10%, 50Hz Star Rating: 5 Inverter Technology Refrigerant :R410/R 32 Compressor: Rotary /Scroll Condenser & Evaporator Coil: Copper (Units shall be supplied with all accessories provided by the manufacturer (i.e. Cu Pipe, Remote, Manuals, Warranty, etc) Make: LG/Daikin/Voltas/Blue Star/Equivalent Approved	Units	4		
2	Installation. Testing and commissioning of above 1.5 TR Split Hi wall Air Conditioning indoor & outdoor unit (i.e. Sl.No.1)	No	4		
3	Supply and installation of suitable size MS Stand for Outdoor unit of above 1.5 TR Split Air Conditioning unit (i.e. for Sl.No.1)	Set	4		
4	Supply, Installation, Testing and Commissioning of Additional Cu piping (as recommended by Manufacturer) for supply and return of refrigerant suitable for Sr. No. 1 Split Hi Wall ACs with 19 mm thick class 'O' nitrile rubber insulation	Mtrs	10		
5	Supply & Installation of 1" Heavy Duty PVC Pipe for drain	Mtrs	10		
6	Supply, Installation, Testing and Commissioning of suitable timer controller for sequence operation of above mentioned Sr. 1 Air Conditioners	Nos	2		
7	Supply, laying, termination, testing & commissioning of 4C X 2.5 sq.mm FR PVC insulated copper conductor flexible cable as per IS 694 with latest amendments	Mtrs	20		
				Basic price	
				GST @ 28% for Supply on ITEM NO.1	
				GST @ 18% for Supply & Instllation on ITEMS 2 TO 7	
				TOTAL VALUE FOR SUPPLY & INSTALLATION (INCLUSIVE OF ALL TAXES)	
	Note: All Rates are all inclusive of Profit, Packing & Forwarding, Transport, loading & Unloading, labour and Taxes, Etc.				