

टाटा मूलभूत अनुसंधान संस्थान, हैदराबाद ।
TATA INSTITUTE OF FUNDAMENTAL RESEARCH, HYDERABAD.

प्लॉट नं. ३६/पी, गोपनपल्ली ग्राम, सेरिलिंगमपल्ली मंडल, रंगा रेड्डी जिला,
हैदराबाद – ५०० १०७, तेलंगाना.
Plot No.36/P, Gopanpally Village, Serilingampally Mandal, Ranga Reddy District, Hyderabad
- 500 107, Telangana, India.

तकनीकी सेवाएँ विभाग / Technical Services Department

तिथि / Date: 02/05/2025

विषय / Subject: प्रि-बिड मीटिंग का मिनट्स / Minutes of the Pre-Bid meeting

निविदा संदर्भ संख्या / Tender Ref. No. TIFR/PD/CF25-14/250031

निविदा की तिथि / Tender Date: 28/04/2025

निविदा विवरण / Tender Description: Supply, Installation, Testing And Commissioning of Process chillers and related works petawatt laser facility at TIFR, Hyderabad.

नोट्स / Notes: The Pre-Bid meeting has held on 02-05-2025 from 11:00 Hrs. to 12:30 Hrs. via zoom for the aforementioned Public Tender.

S.No	Supplier Name	Pre-Bid Meeting Queries from Suppliers	TIFR, Hyderabad response to Supplier Queries
1.	TOOT MNE TECH PVT LTD	The Agencies/Contractors should have executed similar installations of Process chillers and related works at least.– Can we submit the tender with SITC of a chilled water system with Air cooled chiller, pumps,ms pipes and low side, pls confirm	Any chilled water based HVAC installation works will be considered.
2.		As per boq it specifies Air Cooled Scroll Chiller and in technical specification it is mentioned Air Cooled Screw chiller - Can we Consider as per boq only.(scroll chiller):	Yes, Air cooled chillers shall be Scroll type only.
3.		Chiller pedestal and pump pedestal will be supplied by client _ pls confirm.	TIFR will provide the civil pedestals.
4.		Do we need to consider Chiller factory inspection along with 4 point load or normal factory inspection is sufficient.- pls confirm.	Yes, Factory inspection shall be arranged by contractor with 4 point load testing.
5.		Pls share the type of support required for installation of SS 304 piping, as the Routing of the pipe is above ground, or pls add the sufficient structure quantity in the boq line item.	Piping shall be with MS angles as mentioned in the tender. No extra item shall be considered. Contractor shall quote the rate for piping includes required M.S.Supports.

टाटा मूलभूत अनुसंधान संस्थान, हैदराबाद I
TATA INSTITUTE OF FUNDAMENTAL RESEARCH, HYDERABAD.

प्लॉट नं. ३६/पी, गोपनपल्ली ग्राम, सेरिलिंगमपल्ली मंडल, रंगा रेड्डी जिला,
हैदराबाद – ५०० १०७, तेलंगाना.
Plot No.36/P, Gopanpally Village, Serilingampally Mandal, Ranga Reddy District, Hyderabad
- 500 107, Telangana, India.

6.		As per the site visit we get to know that pumps are outside the building, and they are not with IP 65 Protection.	Pumps will be installed under the roof. So pumps are indoor type.
7.		Pls confirm the boq s.no 26 is 2 WAY OR 3 WAY VALVE to consider.	It is a 2 way valve.
8.		Boq Sno 36 and 37 mentioned Quantity and R/O both. Please confirm whether we need to consider Quantity or R/O.	Yes, shall consider the rates and execute the items if required. <i>as a note only</i> <i>as per the tend</i> <i>evaluation</i>

मांगकर्ता / Indenter


प्रमुख, तकनीकी सेवा विभाग /
Head, Technical Services Department

