

TATA INSTITUTE OF FUNDAMENTAL RESEARCH, HYDERABAD

An Autonomous Institution of the Department of Atomic Energy, Government of India (A Deemed University)

Plot No.36/P, Gopanpally Village, Serilingampally Mandal, Ranga Reddy District, Hyderabad, Telangana, India. PIN 500 107

Phone: 040-20203010, Email: rajasekharr@tifrh.res.in

LIMITED TENDER ENQUIRY

Ref: TIFR/PD/CA26-2/260007

April 21, 2026

1. M/s. ARSHI AIR ENTERPRISES (AAEN)
2. M/s. ACREF SOLUTION PRIVATE LIMITED (ACRF)
3. M/s. INTEGRATED COOLTECH PVT. LTD (INCO)
4. M/s. JALEEL AIRCON PROJECTS & SERVICES PVT LTD (JAPS)
5. M/s. ONE IN ALL POINT OF SOLUTIONS (OIAP)
6. M/s. STANDARD COOLING & AIR CONDITIONING (SCAC)
7. M/s. TOOT MNE TECH PRIVATE LIMITED (TOOT)

Dear Sirs

Please let us have your **Quotation** for the following:

S.No.	Item Code	Description	Qty	UOM
1	LCLAD000013	Supply ,Installation,Testing Comissioning of 10TR 4row chilled water colis with copper tubes aluminum hydrophilic coated fins in the 5000CFM ceiling suspended unit .Coil to be selected for Hyderabad conditions.Coil Dinensions:1300mmLength*600mmWidth*150mmDepth	1.00	NO
2	LCLAD000014	Supply ,Insatallation,Testing and Commiissioning of single skin cabinet type inline fan of capcaity 4000CFM and 30mm WC static.Fan should be installed in return air ducting above the SB-1 first floor ceiling.	1.00	NO
3	LCLAD000015	Supply, Installation,Testing and Commissioning of GSS made volume control damper with opposed blades, frame shall be made of 18G GSS and blades shall be made of 20G aluminium aerofoil low leakage type and volume control of 0-100% complete with neoprene rubber gasket, nuts, bolts, screws linkages, flanges etc.	0.50	SQMTR
4	LCLAD000016	Supply and Installation of New Pre Filters Grade :G4/EU4, MERV : 7-8 efficiency : 90% 10 micron, Media: Non-Woven Synthetic media sandwiched by two layers of HDPE and Aluminium mesh, MOC: Aluminium Box type IPD: 4- 5 mmwc, FPD: 12-13 mmwc Temp: Ambient Tested as per EN 779 ASHRAE 52.2 Size: HxWxD : 600x600x50mm	2.00	NOS
5	LCLAD000017	Supply, Installation, Testing and Commissioning of GSS ducting square / rectangular/Round Factory Fabricated Ducting (120GSM) of thickness 0.63 mm sheet (24G) complete with gaskets, elbows, splitters, vanes, cowls, supports arrangement using GI full threaded rods and slotted rails as per drawings, air distribution specifications and requirements. Ducts are joined with suitable nuts, bolts, gaskets etc., Proper care shall be taken to avoid noise and vibrations.	5.00	SQMTR
6	LCLAD000018	Supply and making of 20G GI compartment for chilled water coil ,filters and GI drain tray as per the coil dimensions 1200mmLength*510mmWidth for 5000CFM ceiling suspended unit.	1.00	LOT
7	LCLAD000019	Removing,Re-routing and Fabrication of 25MM dia existing chilled water line and connected to 5000CFM ceiling suspended unit in the AHU room.	1.00	LOT
8	LCLAD000020	Supply, installation of GI Collar Damper with black colour powder coated of size 610mm*610mm	12.00	NOS

Please mention your GST Registration numbers on the quotation, proforma Invoice and Bills.

Quotation should indicate make, delivery period, guarantee/warranty exact taxes applicable, etc.

The payment will be made only after delivery of the supply, satisfactory installation, commissioning and performance of the item/equipment. No Advance payment will be made except in case of furnishing valid Bank Guarantee from any nationalized/scheduled bank the B. G. shall be valid till the complete delivery is made at the site.

Time is the essence of the contract. The delivery of Goods or performance of the Services shall be made by the Supplier in accordance with the time schedule specified in the Purchase Order/Contract.

If the Supplier fails to deliver any or all of the Goods or to perform services within the period(s) specified in the Purchase Order/Contract, the Purchaser shall, without prejudice to other remedies under the Contract, deduct from the Contract Price, as penalty, a sum equivalent to 0.5% per week and the maximum deduction is 10% of the contract price.

Quotation sent by hand delivery / courier are to be deposited in the Tender Box kept at the Main Gate after obtaining stamp, date and signature of the Security Officer.

Quotation should be submitted in sealed envelope duly superscribing our enquiry reference and due date.

Due Date for submitting your offer is 28/04/2026.

Yours faithfully



Rajasekhar R,
Head-Technical Services

Ref no : TIFR/PD/CA26-2/260007

Sr. No.	Item Description	Qty.	UOM	Rate per unit	Item wise GST %	Total Cost including GST (In INR)
1	Supply ,Installation,Testing Comissioning of 10TR 4row chilled water colis with copper tubes aluminum hydrophilic coated fins in the 5000CFM ceiling suspended unit .Coil to be selected for Hyderabad conditions.Coil Dinemsions:1300mmLength*600mmWidth*150mmDept	1	NO			
2	Supply ,Insatallation,Testing and Commiissioning of single skin cabinet type inline fan of capcaity 4000CFM and 30mm WC static.Fan should be installed in return air ducting above the SB-1 first floor ceiling.	1	NO			
3	Supply, Installation,Testing and Commissioning of GSS made volume control damper with opposed blades, frame shall be made of 18G GSS and blades shall be made of 20G aluminium aerofoil low leakage type and volume control of 0-100% complete with neoprene rubber gasket, nuts, bolts, screws linkages, flanges etc.	0.5	SQM TR			
4	Supply and Installation of New Pre Filters Grade :G4/EU4, MERV : 7-8 efficiency : 90% 10 micron, Media: Non-Woven Synthetic media sandwiched by two layers of HDPE and Aluminium mesh, MOC: Aluminium Box type IPD: 4- 5 mmwc, FPD: 12-13 mmwc Temp: Ambient Tested as per EN 779 ASHRAE 52.2 Size: HxWxD : 600x600x50mm	2	NOS			
5	Supply, Installation, Testing and Commissioning of GSS ducting square / rectangular/Round Factory Fabricated Ducting (120GSM) of thickness 0.63 mm sheet (24G) complete with gaskets, elbows, splitters, vanes, cowls, supports arrangement using GI full threaded rods and slotted rails as per drawings, air distribution specifications and requirements. Ducts are joined with suitable nuts, bolts, gaskets etc., Proper care shall be taken to avoid noise and vibrations.	5	SQM TR			
6	Supply and making of 20G GI compartment for chilled water coil ,filters and GI drain tray as per the coil dimensions	1	LOT			

Ref no : TIFR/PD/CA26-2/260007

Sr. No.	Item Description	Qty.	UOM	Rate per unit	Item wise GST %	Total Cost including GST (In INR)
1200mmLength*510mmWidth for 5000CFM ceiling suspended unit.						
7	Removing,Re-routing and Fabrication of 25MM dia existing chilled water line and connected to 5000CFM ceiling suspended unit in the AHU room.	1	LOT			
8	Supply, installation of GI Collar Damper with black colour powder coated of size 610mm*610mm	12	NOS			
Total						
Freight/Transportation charges, if any						
Service/Labour charges, if any						
Any Other charges						
Final Total in figures						
Final total in words						