

TATA INSTITUTE OF FUNDAMENTAL RESEARCH, HYDERABAD

An Autonomous Institution of the Department of Atomic Energy, Government of India (A Deemed University)

Plot No.36/P, Gopanpally Village, Serilingampally Mandal, Ranga Reddy District, Hyderabad, Telangana, India. PIN 500 107

Phone: 040-20203010, Email: rajasekharr@tifrh.res.in

LIMITED TENDER ENQUIRY

Ref: TIFR/PD/CF26-2/260004

April 17, 2026

1. M/s. ACUBE INFRATECH (ACUB)
2. M/s. ARYANATHAN (ARYN)
3. M/s. ELITE ENGINEERS & ENTERPRISES (EES)
4. M/s. HEMANTHASAI CHARAN ELECTRICALS (HSCE)
5. M/s. KAMALAKSHI ENTERPRISES (KAME)
6. M/s. RV CONSTRUCTIONS (RVCO)

Dear Sirs

Please let us have your **Quotation** for the following:

S.No.	Item Code	Description	Qty	UOM
1	LWBWC000002	Providing and laying at or near ground level factory made kerb stone of size 600x375x100mm M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5 mm), including making drainage opening wherever required complete etc. as per direction of Engineer in-charge (length of finished kerb edging shall be measured to calculate volume for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge). Length of the kerb stone laying 160 m ;(160x0.1x0.375=6.0 Cum)	6.00	CUM
2	LWBWC000003	Providing and laying Cement concrete for kerb stone Haunching placed at the rear side of the kerb for a total length of 160 m with 200mm width and 100 mm depth with 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) (160x0.20x0.20/2=3.20 Cum)	3.20	CUM
3	LWBWC000004	Finishing kerb stone walls with synthetic enamel paint of approved brand and manufacture to give an even shade	150.00	SQMTR

Please mention your GST Registration numbers on the quotation, proforma Invoice and Bills.

Quotation should indicate make, delivery period, guarantee/warranty exact taxes applicable, etc.

The payment will be made only after delivery of the supply, satisfactory installation, commissioning and performance of the item/equipment. No Advance payment will be made except in case of furnishing valid Bank Guarantee from any nationalized/scheduled bank the B. G. shall be valid till the complete delivery is made at the site.

Time is the essence of the contract. The delivery of Goods or performance of the Services shall be made by the Supplier in accordance with the time schedule specified in the Purchase Order/Contract.

If the Supplier fails to deliver any or all of the Goods or to perform services within the period(s) specified in the Purchase Order/Contract, the Purchaser shall, without prejudice to other remedies under the Contract, deduct from the Contract Price, as penalty, a sum equivalent to 0.5% per week and the maximum deduction is 10% of the contract price.

Quotation sent by hand delivery / courier are to be deposited in the Tender Box kept at the Main Gate after obtaining stamp, date and signature of the Security Officer.

Quotation should be submitted in sealed envelope duly superscribing our enquiry reference and due date.

Due Date for submitting your offer is 24/04/2026.

Yours faithfully



Rajasekhar R,
Head-Technical Services

Copy to: **Prof. / Dr. / Mr. / Mrs. / Ms. / Shri / Smt. ANAVENA KISHOR (TCIS-26N534)**
Your Indent Req. No.AKA2050011 Dated:17/04/2026 refers.

Remarks: The estimated cost is inclusive of GST @18%

Ref no : TIFR/PD/CF26-2/260004

Sr. No.	Item Description	Qty.	UOM	Rate per unit	Item wise GST %	Total Cost including GST (In INR)
1	Providing and laying at or near ground level factory made kerb stone of size 600x375x100mm M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5 mm), including making drainage opening wherever required complete etc. as per direction of Engineer in-charge (length of finished kerb edging shall be measured to calculate volume for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).Length of the kerb stone laying 160 m ;(160x0.1x0.375=6.0 Cum)	6	CUM			
2	Providing and laying Cement concrete for kerb stone Haunching placed at the rear side of the kerb for a total length of 160 m with 200mm width and 100 mm depth with 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) (160x0.20x0.20/2=3.20 Cum)	3.2	CUM			
3	Finishing kerb stone walls with synthetic enamel paint of approved brand and manufacture to give an even shade	150	SQM TR			

Ref no : TIFR/PD/CF26-2/260004

Sr. No.	Item Description	Qty.	UOM	Rate per unit	Item wise GST %	Total Cost including GST (In INR)
	Total					
	Freight/Transportation charges, if any					
	Service/Labour charges, if any					
	Any Other charges					
	Final Total in figures					
	Final total in words					