

TATA INSTITUTE OF FUNDAMENTAL RESEARCH, HYDERABAD

An Autonomous Institution of the Department of Atomic Energy, Government of India (A Deemed University)

Plot No.36/P, Gopanpally Village, Serilingampally Mandal, Ranga Reddy District. Hyderabad, Telangana, India. PIN 500 107

Phone: 040-2020-3010, Email: rajasekharr@tifrh.res.in

ENQUIRY

Ref: TIFR/PD/CF25-157/251804

January 30, 2026

1. M/s. ACUBE INFRATECH (ACUB)
2. M/s. ARYANATHAN (ARYN)
3. M/s. HEMANTHASAI CHARAN ELECTRICALS (HSCE)
4. M/s. KAMALAKSHI ENTERPRISES (KAME)
5. M/s. RV CONSTRUCTIONS (RVCO)
6. M/s. SRI SAI SHIVAAJI ENTERPRISES. (SASH)

Dear Sirs

Please let us have your **Quotation** for the following:

S.No.	Item Code	Description	Qty	UOM
1	LSWMS003377	Providing and laying 60 mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design shape, laid in required colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	91.43	SQMT
2	LSWMS003378	Providing and laying cement concrete with 1:2:4 (1 Cement: 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources) for rigid edging around the perimeter to prevent the pavers from shifting outward and for levelling the platform	6.68	CUM
3	LSWMS003379	Removal and refixing of existing interlocking paver blocks of any design/shape laid in required line, level, curvature, color and pattern over and including 50 mm thick compacted bed of coarse sand filling the joints with fine sand etc all complete as per the direction of Engineer in charge.	18.25	SQMT
4	LSWMS003380	Chipping of existing concrete surface to a depth of 100 mm of 1.5 sqm area approx. including cleaning and removal from the site.	1.00	LS

Please mention your GST Registration numbers on the quotation, proforma Invoice and Bills.

Quotation should indicate make, delivery period, guarantee/warranty exact taxes applicable, etc.

The payment will be made only after delivery of the supply, satisfactory installation, commissioning and performance of the item/equipment. No Advance payment will be made except in case of furnishing valid Bank Guarantee from any nationalized/scheduled bank the B. G. shall be valid till the complete delivery is made at the site.

Time is the essence of the contract. The delivery of Goods or performance of the Services shall be made by the Supplier in accordance with the time schedule specified in the Purchase Order/Contract.

If the Supplier fails to deliver any or all of the Goods or to perform services within the period(s) specified in the Purchase Order/Contract, the Purchaser shall, without prejudice to other remedies under the Contract, deduct from the Contract Price, as penalty, a sum equivalent to 0.5% per week and the maximum deduction is 10% of the contract price.

Quotation sent by hand delivery / courier are to be deposited in the Tender Box kept at the Main Gate after obtaining stamp, date and signature of the Security Officer.

Quotation should be submitted in sealed envelope duly superscribing our enquiry reference and due date.

Due Date for submitting your offer is 09/02/2026.

Yours faithfully

The image shows a handwritten signature in blue ink, which appears to be 'Rajasekhar R.', next to a circular blue ink stamp. The stamp contains the text 'T.I.F.R.' at the top, 'HYDERABAD-500 046' at the bottom, and two stars on either side of the center.

Rajasekhar R,
Head-Technical Services

Copy to: Prof. / Dr. / Mr. / Mrs. / Ms. / Shri / Smt. ANAVENA KISHOR (TCIS-19P2112)
Your Indent Req. No.AKA2050006 Dated:29/01/2026 refers.

Remarks: The estimated cost is inclusive of GST @18%

Ref no : TIFR/PD/CF25-157/251804

Sr. No.	Item Description	Qty.	UOM	Rate per unit	Item wise GST %	Total Cost including GST (In INR)
1	Providing and laying 60 mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design shape, laid in required colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	91.43	SQM T			
2	Providing and laying cement concrete with 1:2:4 (1 Cement: 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources) for rigid edging around the perimeter to prevent the pavers from shifting outward and for levelling the platform	6.68	CUM			
3	Removal and refixing of existing interlocking paver blocks of any design/shape laid in required line, level, curvature, color and pattern over and including 50 mm thick compacted bed of coarse sand filling the joints with fine sand etc all complete as per the direction of Engineer in charge.	18.25	SQM T			
4	Chipping of existing concrete surface to a depth of 100 mm of 1.5 sqm area approx. including cleaning and removal from the site.	1	LS			

Ref no : TIFR/PD/CF25-157/251804

Sr. No.	Item Description	Qty.	UOM	Rate per unit	Item wise GST %	Total Cost including GST (In INR)
	Total					
	Freight/Transportation charges, if any					
	Service/Labour charges, if any					
	Any Other charges					
	Final Total in figures					
	Final total in words					