

# TATA INSTITUTE OF FUNDAMENTAL RESEARCH, HYDERABAD

An Autonomous Institution of the Department of Atomic Energy, Government of India (A Deemed University)

Plot No.36/P, Gopanpally Village,Serilingampally Mandal,Ranga Reddy District. Hyderabad,Telangana, India.PIN 500 107

Phone: 040-2020-3010, Email: rajasekharr@tifrh.res.in

## ENQUIRY

Ref: TIFR/PD/CF25-163/251837

February 04, 2026

1. M/s. A GOVERDHAN (AGOV)
2. M/s. CHARAN ELECTRICALS (CHEL)
3. M/s. ELITE ENGINEERS & ENTERPRISES (EES)
4. M/s. HEMANTHASAI CHARAN ELECTRICALS (HSCE)
5. M/s. KVM ELECTRICALS (KVME)
6. M/s. SDV SRINIVAS (SDVS)
7. M/s. SAI SRINIVASA ELECTRICALS (SRIE)
8. M/s. VINAY TECHNICAL WORKS (VTCW)

Dear Sirs

Please let us have your **Quotation** for the following:

S.No.	Item Code	Description	Qty	UOM
1	LSWMS003383	"Supply, installation , testing   commissioning of 8Way Ready Made VTPN Distribution Board along with 25KA, 415V, 250A Thermal Magnetic MCCB-1 No as incoming including Spreader links and C type 415V, 63A TP MCBs- 8 Nos as outgoing. Distribution Board shall be surface/recess mounting, made of sheet steel, dust protected, duly powder painted and double door type. VTPN DB shall have the provision of 250A Copper Bus bar for each phase, 2 neutral bars and 2 earth bars. VTPN DB shall be IP43 and as per IEC 61439-3.VTPN DB shall be equivalent to Legrand Catalogue No. 5077 59 , MCCB shall be equivalent to Legrand Catalogue No. 4202 19 and MCB shall be equivalent to Legrand Catalogue No. 4086 61. (Make : Legrand/ ABB/Siemens /Schneider /equivalent approved )";	1.00	SET
2	LSWMS003384	Supply, installation , testing   commissioning of 6Way Ready Made TPN Distribution Boards shall be surface/recess mounting vertical/horizontal type, 415 volts TPN MCB for Incoming, distribution board of sheet steel, dust protected ,duly powder painted, inclusive of 100 amps tinned copper interconnections with appropriate capacity size of PVC insulated copper conductor wires (ISI marked) suitable for mounting necessary isolators / MCBs/ ELCBs etc., and suitable for concealed mounting /wall mounting with M.S enclosure fabricated out of min 18 SWG/20 SWG thick M.S CRCA sheet as per manufacturers standard, with concealed hinged door locking arrangement etc., including earthing clamps ,common neutral link, earth bar, din bar for mounting MCB's (but without MCB's ) as required as per IS:13032 and IEC 60647-2 equivalent to Legrand Cat No.5076 71 (Make : Legrand/ ABB/ Siemens /equivalent approved )	1.00	NO
3	LSWMS003385	"Supply, installation , testing   commissioning of ISI Marked and accepted standard of 63A, FP Miniature Circuit Breaker (MCB) of 'C' series suitable for 240/415 Volts AC , 50Hz, 10kA confirming to IS: 8828 : 1996, IEC: 60898-1 : 2002. MCBs and Distribution Boards should be the same make only. (Make: Legrand/ ABB/ Siemens/Schneider ) (Equivalent to Legrand Catalog No. 4087 02 "	1.00	NO
4	LSWMS003386	Supply, installation , testing   commissioning of ISI Marked and accepted standard of 32A, FP Miniature Circuit Breaker (MCB) of 'C' series suitable for 240/415 Volts AC , 50Hz, 10kA confirming to IS: 8828 : 1996, IEC: 60898-1 : 2002. MCBs and Distribution Boards should be the same make only. (Make: Legrand/ ABB/ Siemens/Schneider ) (Equivalent to Legrand Catalog No. 4086 99	3.00	NO
5	LSWMS003387	"Supply, installation , testing   commissioning of ISI Marked and accepted standard of 16A, FP Miniature Circuit Breaker (MCB) of 'C' series suitable for	1.00	NO

LSWMS003387 240/415 Volts AC , 50Hz, 10kA confirming to IS: 8828 : 1996, IEC: 60898-1 : 2002. MCBs and Distribution Boards should be the same make only. (Make: Legrand/ ABB/ Siemens/Schneider ) Equivalent to Legrand Catalog No. 4086 96  
"

6	LSWMS003388	Supply, installation , testing   commissioning of ISI Marked and accepted standard of 16A, SP Miniature Circuit Breaker (MCB) of 'C' series suitable for 240/415 Volts AC , 50Hz, 10kA confirming to IS: 8828 : 1996, IEC: 60898-1 : 2002. MCBs and Distribution Boards should be the same make only. (Make: Legrand/ ABB/ Siemens/Schneider ) Equivalent to Legrand Catalog No. 4085 92	18.00	NO
7	LSWMS003389	Supply, laying, testing   commissioning of 1100V, 4C X 35 sq.mm FR PVC insulated copper conductor flexible cable as per IS 694 with latest amendments   as per technical specifications. Cable shall be laid on the wall/ceiling through PVC conduits and as per the instructions of E.I.C. Make: Polycab/Havells/Finolex/RR Cables	2.00	MTR
8	LSWMS003390	Supply, Installation of suitable single compression PVC Gland, Copper Lugs and accessories for termination of cable mentioned in Sr. No.7 in the Distribution Board.	2.00	SET
9	LSWMS003391	Supply, laying, testing   commissioning of 1100V, 5C X 16 sq.mm FR PVC insulated copper conductor flexible cable as per IS 694 with latest amendments   as per technical specifications. Cable shall be laid on the wall/ceiling through PVC conduits and as per the instructions of E.I.C. Make: Polycab/Havells/Finolex/RR Cables	150.00	MTR
10	LSWMS003392	Supply, Installation of suitable single compression PVC Gland, Copper Lugs and accessories for termination of cable mentioned in Sr. No.9 in the Distribution Board.	12.00	SET
11	LSWMS003393	Supply, laying, testing   commissioning of 1100V, 5C X 6 sq.mm FR PVC insulated copper conductor flexible cable as per IS 694 with latest amendments   as per technical specifications. Cable shall be laid on the wall/ceiling through PVC conduits and as per the instructions of E.I.C. Make: Polycab/Havells/Finolex/RR Cables	50.00	MTR
12	LSWMS003394	Supply, Installation of suitable single compression PVC Gland, Copper Lugs and accessories for termination of cable mentioned in Sr. No.11 in the Distribution Board.	4.00	SET
13	LSWMS003395	Supply, laying, termination, testing   commissioning of 1100V, 3C X 4 sq.mm FR PVC insulated copper conductor Flexible cable as per IS 694 with latest amendments for power circuits and laying on existing Concealed PVC Conduit on wall or False ceiling including suitable copper lugs for termination in DBs Make:Polycab/Havells/Finolex/RR Cables/equivalent approved	50.00	MTR
14	LSWMS003396	"Supply , Fixing, Testing and Commissioning of 6 modular switch board (16A Sockets -2No,   20/16A Switches -2Nos Indicator type ) with suitable Metal flush Box and cover plates with interconnections. Switch Boards shall be concealed on the wall. (Make: Legrand /MK/ Equivalent to M/s. Legrand Catalogue No. 5734 71   5720 63 )"	2.00	SET

Please mention your GST Registration numbers on the quotation, proforma Invoice and Bills.

Quotation should indicate make, delivery period, guarantee/warranty exact taxes applicable, etc.

The payment will be made only after delivery of the supply, satisfactory installation, commissioning and performance of the item/equipment. No Advance payment will be made except in case of furnishing valid Bank Guarantee from any nationalized/scheduled bank the B. G. shall be valid till the complete delivery is made at the site.

Time is the essence of the contract. The delivery of Goods or performance of the Services shall be made by the Supplier in accordance with the time schedule specified in the Purchase Order/Contract.

If the Supplier fails to deliver any or all of the Goods or to perform services within the period(s) specified in the Purchase Order/Contract, the Purchaser shall, without prejudice to other remedies under the Contract, deduct from the Contract Price, as penalty, a sum equivalent to 0.5% per week and the maximum deduction is 10 % of the contract price.

Quotation sent by hand delivery / courier are to be deposited in the Tender Box kept at the Main Gate after obtaining stamp, date and signature of the Security Officer.

**Quotation should be submitted in sealed envelope duly superscribing our enquiry reference and due date.**

**Due Date for submitting your offer is 16/02/2026.**

**Yours faithfully**



Rajasekhar R,  
Head-Technical Services

**Copy to: Prof. / Dr. / Mr. / Mrs. / Ms. / Shri / Smt. ELLABOINA VINAY (TCIS-19P2099)  
Your Indent Req. No.EVA0010003 Dated:21/01/2026 refers.**

Ref no : TIFR/PD/CF25-163/251837

Sr. No.	Item Description	Qty.	UOM	Rate per unit	Item wise GST %	Total Cost including GST (In INR)
1	"Supply, installation , testing   commissioning of 8Way Ready Made VTPN Distribution Board along with 25KA, 415V, 250A Thermal Magnetic MCCB-1 No as incomer including Spreader links and C type 415V, 63A TP MCBs- 8 Nos as outgoing. Distribution Board shall be surface/recess mounting, made of sheet steel, dust protected, duly powder painted and double door type. VTPN DB shall have the provision of 250A Copper Bus bar for each phase, 2 neutral bars and 2 earth bars. VTPN DB shall be IP43 and as per IEC 61439-3.VTPN DB shall be equivalent to Legrand Catalogue No. 5077 59 , MCCB shall be equivalent to Legrand Catalogue No. 4202 19 and MCB shall be equivalent to Legrand Catalogue No. 4086 61. (Make : Legrand/ ABB/Siemens /Schneider /equivalent approved )"¿	1	SET			
2	Supply, installation , testing   commissioning of 6Way Ready Made TPN Distribution Boards shall be surface/recess mounting vertical/horizontal type, 415 volts TPN MCB for Incoming, distribution board of sheet steel, dust protected ,duly powder painted, inclusive of 100 amps tinned copper interconnections with appropriate capacity size of PVC insulated copper conductor wires (ISI marked) suitable for mounting necessary isolators / MCBs/ ELCBs etc., and suitable for concealed mounting /wall mounting with M.S enclosure fabricated out of min 18 SWG/20 SWG thick M.S CRCA sheet as per manufacturers standard, with concealed hinged door locking arrangement etc., including earthing clamps ,common neutral link, earth bar, din bar for mounting MCB's (but without MCB's ) as required as per IS:13032 and IEC 60647-2 equivalent to Legrand Cat No.5076 71 (Make : Legrand/ ABB/ Siemens /equivalent approved )	1	NO			
3	"Supply, installation , testing   commissioning of ISI Marked and accepted standard of 63A, FP Miniature Circuit Breaker (MCB) of 'C' series suitable for 240/415 Volts AC , 50Hz, 10kA	1	NO			

Sr. No.	Item Description	Qty.	UOM	Rate per unit	Item wise GST %	Total Cost including GST (In INR)
	confirming to IS: 8828 : 1996, IEC: 60898-1 : 2002. MCBs and Distribution Boards should be the same make only. (Make: Legrand/ ABB/ Siemens/Schneider ) (Equivalent to Legrand Catalog No. 4087 02 "					
4	Supply, installation , testing   commissioning of ISI Marked and accepted standard of 32A, FP Miniature Circuit Breaker (MCB) of 'C' series suitable for 240/415 Volts AC , 50Hz, 10kA confirming to IS: 8828 : 1996, IEC: 60898-1 : 2002. MCBs and Distribution Boards should be the same make only. (Make: Legrand/ ABB/ Siemens/Schneider ) (Equivalent to Legrand Catalog No. 4086 99	3	NO			
5	"Supply, installation , testing   commissioning of ISI Marked and accepted standard of 16A, FP Miniature Circuit Breaker (MCB) of 'C' series suitable for 240/415 Volts AC , 50Hz, 10kA confirming to IS: 8828 : 1996, IEC: 60898-1 : 2002. MCBs and Distribution Boards should be the same make only. (Make: Legrand/ ABB/ Siemens/Schneider ) Equivalent to Legrand Catalog No. 4086 96 "	1	NO			
6	Supply, installation , testing   commissioning of ISI Marked and accepted standard of 16A, SP Miniature Circuit Breaker (MCB) of 'C' series suitable for 240/415 Volts AC , 50Hz, 10kA confirming to IS: 8828 : 1996, IEC: 60898-1 : 2002. MCBs and Distribution Boards should be the same make only. (Make: Legrand/ ABB/ Siemens/Schneider ) Equivalent to Legrand Catalog No. 4085 92	18	NO			
7	Supply, laying, testing   commissioning of 1100V, 4C X 35 sq.mm FR PVC insulated copper conductor flexible cable as per IS 694 with latest amendments   as per technical specifications. Cable shall be laid on the wall/ceiling through PVC conduits and as per the instructions of E.I.C. Make: Polycab/Havells/Finolex/RR Cables	2	MTR			
8	Supply, Installation of suitable single compression PVC Gland, Copper Lugs and accessories for termination of cable mentioned in Sr. No.7 in the Distribution Board.	2	SET			

Sr. No.	Item Description	Qty.	UOM	Rate per unit	Item wise GST %	Total Cost including GST (In INR)
9	Supply, laying, testing   commissioning of 1100V, 5C X 16 sq.mm FR PVC insulated copper conductor flexible cable as per IS 694 with latest amendments   as per technical specifications. Cable shall be laid on the wall/ceiling through PVC conduits and as per the instructions of E.I.C. Make: Polycab/Havells/Finolex/RR Cables	150	MTR			
10	Supply, Installation of suitable single compression PVC Gland, Copper Lugs and accessories for termination of cable mentioned in Sr. No.9 in the Distribution Board.	12	SET			
11	Supply, laying, testing   commissioning of 1100V, 5C X 6 sq.mm FR PVC insulated copper conductor flexible cable as per IS 694 with latest amendments   as per technical specifications. Cable shall be laid on the wall/ceiling through PVC conduits and as per the instructions of E.I.C. Make: Polycab/Havells/Finolex/RR Cables	50	MTR			
12	Supply, Installation of suitable single compression PVC Gland, Copper Lugs and accessories for termination of cable mentioned in Sr. No.11 in the Distribution Board.	4	SET			
13	Supply, laying, termination, testing   commissioning of 1100V, 3C X 4 sq.mm FR PVC insulated copper conductor Flexible cable as per IS 694 with latest amendments for power circuits and laying on existing Concealed PVC Conduit on wall or False ceiling including suitable copper lugs for termination in DBs Make:Polycab/Havells/Finolex/RR Cables/equivalent approved	50	MTR			
14	"Supply , Fixing, Testing and Commissioning of 6 modular switch board (16A Sockets -2No,   20/16A Switches -2Nos Indicator type ) with suitable Metal flush Box and cover plates with interconnections. Switch Boards shall be concealed on the wall. (Make: Legrand /MK/ Equivalent to M/s. Legrand Catalogue No. 5734 71   5720 63 )"	2	SET			

Ref no : TIFR/PD/CF25-163/251837

Sr. No.	Item Description	Qty.	UOM	Rate per unit	Item wise GST %	Total Cost including GST (In INR)
	Total					
	Freight/Transportation charges, if any					
	Service/Labour charges, if any					
	Any Other charges					
	Final Total in figures					
	Final total in words					