

TATA INSTITUTE OF FUNDAMENTAL RESEARCH, HYDERABAD

An Autonomous Institution of the Department of Atomic Energy, Government of India (A Deemed University)

Plot No.36/P, Gopanpally Village, Serilingampally Mandal, Ranga Reddy District. Hyderabad, Telangana, India. PIN 500 107

Phone: 040-2020-3010, Email: rajasekharr@tifrh.res.in

ENQUIRY

Ref: TIFR/PD/CF25-145/251733

January 19, 2026

1. M/s. ACUBE INFRATECH (ACUB)
2. M/s. ARYANATHAN (ARYN)
3. M/s. ELITE ENGINEERS & ENTERPRISES (EES)
4. M/s. ELITE INFRA ASSOCIATES (ELIA)
5. M/s. THE INTERIOR STORE (ITST)
6. M/s. KRANTHI CONSTRUCTIONS (KRAN)

Dear Sirs

Please let us have your **Quotation** for the following:

S.No.	Item Code	Description	Qty	UOM
1	LSWMS003367	Supplying and laying of self levelling base screed material on existing kota stone flooring. The existing flooring surface shall be prepared clean free from dust and dirt and shall be given concentrated water based primer and bonding agent P-51 of M/S ARDEX Endura applied uniformly to receive cement based leveling compound. The unevenness flooring shall be levelled using commercial grade levelling compound of CL11 of M/s ARDEX Endura in thickness 3-5mm to receive ESD Vinyl flooring. The rate shall includes cost of all materials to site, laying and transportation charges etc complete for finished item of work. (actual area of flooring executed shall be considered for payment)	64.76	SQMTR
2	LSWMS003368	Supplying and laying of Antistatic ESD (Electrostatic Discharge) Vinyl flooring over already prepared smooth self levelling screed base surface in item no.1 above. The laying of copper grid in size 1.00 x 1.00 m using copper strip of 10mm and thickness 0.08mm shall be laid on entire floor surface. the anti static ESD flooring in 2mm thick conductive and vinyl sheet shall be laid on prepared copper grid surface, floor material make: Armstrong PASTELL conductive vinyl floor material as per manufacture specification in 2mm thick roles of selected conductive 2316-201 Vintage cream width and bonding using AROBOUND-43 water based synthetic adhesive for base floor to vinyl floor. The longitudinal joints of floor shall be welded properly. The laying of flooring shall be as per manufacturer specification. the agency shall submit test report on conductive vinyl flooring laid w.r.t parameters such as thickness, hardness, surface resistance and volume resistance etc mentioned by manufacturer. the vinyl sheet shall be laid also on to coving up to a height of 4" on walls and columns. the rates shall includes cost of all materials to site, laying and transportation charges etc complete for finished item of work. (actual area of flooring executed shall be considered for payment)	66.04	SQMTR

Please mention your GST Registration numbers on the quotation, proforma Invoice and Bills.

Quotation should indicate make, delivery period, guarantee/warranty exact taxes applicable, etc.

The payment will be made only after delivery of the supply, satisfactory installation, commissioning and performance of the item/equipment. No Advance payment will be made except in case of furnishing valid Bank Guarantee from any nationalized/scheduled bank the B. G. shall be valid till the complete delivery is made at the site.

Time is the essence of the contract. The delivery of Goods or performance of the Services shall be made by the Supplier in accordance with the time schedule specified in the Purchase Order/Contract.

If the Supplier fails to deliver any or all of the Goods or to perform services within the period(s) specified in the Purchase Order/Contract, the Purchaser shall, without prejudice to other remedies under the Contract, deduct from the Contract Price, as penalty, a sum equivalent to 0.5% per week and the maximum deduction is 10% of the contract price.

Quotation sent by hand delivery / courier are to be deposited in the Tender Box kept at the Main Gate after obtaining stamp, date and signature of the Security Officer.

Quotation should be submitted in sealed envelope duly superscribing our enquiry reference and due date.

Due Date for submitting your offer is 28/01/2026.

Yours faithfully



Rajasekhar R,
Head-Technical Services

Copy to: Prof. / Dr. / Mr. / Mrs. / Ms. / Shri / Smt. ANAVENA KISHOR (TCIS-19P2112)
Your Indent Req. No.AKA2050004 Dated:09/01/2026 refers.

Remarks: RATES ARE INCLUSIVE GST @ 18%

Ref no : TIFR/PD/CF25-145/251733

Sr. No.	Item Description	Qty.	UOM	Rate per unit	Item wise GST %	Total Cost including GST (In INR)
1	Supplying and laying of self levelling base screed material on existing kota stone flooring. The existing flooring surface shall be prepared clean free from dust and dirt and shall be given concentrated water based primer and bonding agent P-51 of M/S ARDEX Endura applied uniformly to receive cement based leveling compound. The unevenness flooring shall be levelled using commercial grade levelling compound of CL11 of M/s ARDEX Endura in thickness 3-5mm to receive ESD Vinyl flooring. The rate shall includes cost of all materials to site, laying and transportation charges etc complete for finished item of work. (actual area of flooring executed shall be considered for payment)	64.76	SQM TR			
2	Supplying and laying of Antistatic ESD (Electrostatic Discharge) Vinyl flooring over already prepared smooth self levelling screed base surface in item no.1 above. The laying of copper grid in size 1.00 x 1.00 m using copper strip of 10mm and thickness 0.08mm shall be laid on entire floor surface. the anti static ESD flooring in 2mm thick conductive and vinyl sheet shall be laid on prepared copper grid surface, floor material make: Armstrong PASTELL conductive vinyl floor material as per manufacture specification in 2mm thick roles of selected conductive 2316-201 Vintage cream width and bonding using AROBOUND-43 water based synthetic adhesive for base floor to vinyl floor. The longitudinal joints of floor shall be welded properly. The laying of flooring shall be as per manufacturer specification. the agency shall submit test report on conductive vinyl flooring laid w.r.t parameters such as thickness, hardness, surface resistance and volume resistance etc mentioned by manufacturer. the vinyl sheet shall be laid also on to coving up to a height of 4" on walls and columns. the rates shall includes cost of all materials to site, laying and transportation charges etc complete for finished item of work. (actual area of flooring executed	66.04	SQM TR			

Ref no : TIFR/PD/CF25-145/251733

Sr. No.	Item Description	Qty.	UOM	Rate per unit	Item wise GST %	Total Cost including GST (In INR)
---------	------------------	------	-----	---------------	-----------------	-----------------------------------

shall be considered for payment)

Total					
Freight/Transportation charges, if any					
Service/Labour charges, if any					
Any Other charges					
Final Total in figures					
Final total in words					