

TATA INSTITUTE OF FUNDAMENTAL RESEARCH, HYDERABAD

An Autonomous Institution of the Department of Atomic Energy, Government of India (A Deemed University)

Plot No.36/P, Gopanpally Village, Serilingampally Mandal, Ranga Reddy District, Hyderabad, Telangana, India. PIN 500 107

Phone: 040-20203010, Email: rajasekharr@tifrh.res.in

LIMITED TENDER ENQUIRY

Ref: TIFR/PD/CF25-187/252116

March 04, 2026

1. M/s. ACUBE INFRATECH (ACUB)
2. M/s. ARYANATHAN (ARYN)
3. M/s. ELITE ENGINEERS & ENTERPRISES (EES)
4. M/s. ELITE INFRA ASSOCIATES (ELIA)
5. M/s. KAMALAKSHI ENTERPRISES (KAME)
6. M/s. RV CONSTRUCTIONS (RVCO)

Dear Sirs

Please let us have your **Quotation** for the following:

S.No.	Item Code	Description	Qty	UOM
1	LSWMS003422	Providing and laying in position ready mixed design mix cement concrete for plain cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana/ Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering and finishing as per direction of the engineer-in-charge; with Concrete of M20 grade with minimum cement content of 270 kg /cum	24.00	CUM
2	LSWMS003423	Providing and laying Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	47.83	SQMTR
3	LSWMS003424	Providing and laying Kota stone slabs 20 mm thick in skirting laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	3.06	SQMTR

Please mention your GST Registration numbers on the quotation, proforma Invoice and Bills.

Quotation should indicate make, delivery period, guarantee/warranty exact taxes applicable, etc.

The payment will be made only after delivery of the supply, satisfactory installation, commissioning and performance of the item/equipment. No Advance payment will be made except in case of furnishing valid Bank Guarantee from any nationalized/scheduled bank the B. G. shall be valid till the complete delivery is made at the site.

Time is the essence of the contract. The delivery of Goods or performance of the Services shall be made by the Supplier in accordance with the time schedule specified in the Purchase Order/Contract.

If the Supplier fails to deliver any or all of the Goods or to perform services within the period(s) specified in the Purchase Order/Contract, the Purchaser shall, without prejudice to other remedies under the Contract, deduct from the Contract Price, as penalty, a sum equivalent to 0.5% per week and the maximum deduction is 10% of the contract price.

Quotation sent by hand delivery / courier are to be deposited in the Tender Box kept at the Main Gate after obtaining stamp, date and signature of the Security Officer.

Quotation should be submitted in sealed envelope duly superscribing our enquiry reference and due date.

Due Date for submitting your offer is 13/03/2026.

Yours faithfully

The image shows a handwritten signature in blue ink on the left, which appears to be 'Rajasekhar R.'. To the right of the signature is a circular blue stamp. The stamp contains the text 'T.I.F.R.' at the top, 'HYDERABAD-500 046' at the bottom, and two small stars on either side of the center.

Rajasekhar R,
Head-Technical Services

Copy to: Prof. / Dr. / Mr. / Mrs. / Ms. / Shri / Smt. ANAVENA KISHOR (TCIS-25N534)
Your Indent Req. No.AKA2050008 Dated:24/02/2026 refers.

Remarks: The estimated cost is inclusive of GST @18%

Ref no : TIFR/PD/CF25-187/252116

Sr. No.	Item Description	Qty.	UOM	Rate per unit	Item wise GST %	Total Cost including GST (In INR)
1	Providing and laying in position ready mixed design mix cement concrete for plain cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana/ Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering and finishing as per direction of the engineer-in-charge; with Concrete of M20 grade with minimum cement content of 270 kg /cum	24	CUM			
2	Providing and laying Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	47.83	SQM TR			
3	Providing and laying Kota stone slabs 20 mm thick in skirting laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	3.06	SQM TR			

Ref no : TIFR/PD/CF25-187/252116

Sr. No.	Item Description	Qty.	UOM	Rate per unit	Item wise GST %	Total Cost including GST (In INR)
	Total					
	Freight/Transportation charges, if any					
	Service/Labour charges, if any					
	Any Other charges					
	Final Total in figures					
	Final total in words					